## CHITALDRUG DISTRICT.

*The 10th February* 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Chitaldrug division, up to 28th February 1898, for restoring Gonur Tank, Registered No. 18, Chitaldrug taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Chitaldrug between the hours of 11 A. M. and 5 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer, and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of Rs. 100 (one hundred) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring the Gonur Tank, Registered No. 18, Chitaldrug taluk"; in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Eastern Circle, who does not bind himself to accept the lowest or any tender, or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which his tender will be considered cancelled and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Abstract estimate of the probable cost of restoring the Gonur Tank, Registered No. 18 of Chitaldrug taluk.

| *Items of work.* | *Per.* | *Quantity.* |
|---|---|---|
| *Bund.* | | |
| Earthwork (including consolidation, &c.) | C. yds. | 30,110 |
| Do do breach | ,, | 14,141 |
| Do (from cutting excavation and tamping, &c.) | ,, | 500 |
| Clearing silt in the breach | Lump sum. | Rs. |
| Baling water and cutting grips | ,, | |
| Re-fixing grade stones | ,, | |
| Clearing bushes, &c., in rear slope | ,, | |
| Picking bund rear slope | ,, | |
| Turfing | S. yds. | 15,400 |
| New stone work | C. yds. | 329 |
| Old stone (dismantling and re-building) | ,, | 200 |
| *Weir.* | | |
| Earthwork | C. yds. | 186 |
| Burnt brick in chunam | C. ft. | 2,675 |
| Burnt stone slabs | S. ft. | 258 |
| Plastering with chunam | Lump sum. | Rs. |
| Rough stone in chunam | C. ft. | 2,109 |
| Pointing with chunam | Lump sum. | Rs. |
| Dismantling the cody and clearing, &c. | ,, | |
| *Sluice.* | | |
| Repairing | Lump sum. | Rs. |

K. PRAHLADA RAO, *Offg. Executive Engineer.*

## BANGALORE DIVISION.

*The 17th February* 1898.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Bangalore Division, up to 5th March 1898, for constructing Students' Home attached to Central College, Bangalore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of December 1899.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Bangalore between the hours of 12 and 4 P. M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer and be accompanied by a statement, in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees five hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for constructing Students' Home attached to Central College, Bangalore, in default of which, tenders will be rejected.